V8 XJ Series/XK

DATE 06/02

303-54

SERVICE

TECHNICAL BULLETIN

Overheating – Thermostat Stuck Closed – Revised Thermostat Available

MODEL

1997-2002 MY XK Range 1998-2002 MY V8 XJ Series

VIN

001001-A30161 812256-F55733

Issue:

Some V8 engines in XJ and XK vehicles within the above VIN ranges (prior to engine number 0203230140) may experience overheating due to the thermostat sticking in the closed position. A revised thermostat with a more robust wax bulb is now available.

Action:

On a customer complaint basis only, follow the workshop procedure outlined below.

WORKSHOP PROCEDURE

- 1. Open the hood and place protective covers over the fenders.
- 2. Raise the vehicle on a lift.
- 3. Place a suitable tray under the front of the vehicle to catch spillage.
- 4. Drain the coolant from the radiator.
- 5. On normally aspirated vehicles only, remove the engine covers.
- 6. On all vehicles, release and reposition hose clip from thermostat housing coolant pipe.
- 7. Disconnect and remove the coolant hose from the thermostat housing.
- 8. Remove thermostat cover bolts (normally aspirated engines, Illustration 1, supercharged engines, Illustration 2).




ILLUSTRATION 1






ILLUSTRATION 2

- 9. Remove thermostat cover from housing.
- 10. Remove thermostat and seal from housing (normally aspirated engines, Illustration 3, supercharged engines, Illustration 4).




ILLUSTRATION 3




ILLUSTRATION 4

JAGUAR

- 11. Install new thermostat and new seal in housing.
- 12. Tighten thermostat cover securing bolts to 8-10 Nm.
- 13. Connect coolant hose to thermostat housing.
- 14. Install hose clip on thermostat housing coolant pipe.
- 15. Install engine covers on normally aspirated vehicles only.
- 16. On all engines, clean spillage from front of engine.
- 17. Remove the tray from under the vehicle.
- 18. Refill the coolant system.
- 19. Remove the fender protector covers and close the hood.

Parts Information:

DESCRIPTION	PART NUMBER	<u>QTY</u>	
Thermostat	AJ8 5874	1	
Thermostat seal	NCA 2246BA	1	

Warranty Information:

Warranty claims should be submitted quoting the information found in the table below. This will result in payment of the stated time and, where applicable parts/miscellaneous expense codes as listed.

Description	SRO	Time	Causal Part Number	Causal Part Description
Install thermostat - XJ series normally aspirated	26.45.07	0.7 hrs.	AJ8 5874	Thermostat
Install thermostat - XJ series supercharged	26.45.07	0.7 hrs.	AJ8 5874	Thermostat
Install thermostat - XK series	26.45.07	0.7 hrs.	AJ8 5874	Thermostat
Install thermostat - XKR	26.45.07	1.0 hrs.	AJ8 5874	Thermostat

